

NOTES:

- USE OF "HIGH PROFILE" BASKET WILL REQUIRE REMOVAL OF BASKET TOP RING(S) AND LOOPS LESS THAN 4-6" BELOW SHOULDER OF ROOT BALL PRIOR TO PLANTING. BURLAP CAN REMAIN.
- AS PART OF THE HARVESTING PROCESS, REMOVE ALL EXCESS SOIL ABOVE STRUCTURAL ROOTS.
- DO NOT LIFT "PACKAGE" BY WIRE BASKET AS IT CAN CAUSE WIRE TO EXTEND ABOVE SHOULDER OF ROOT BALL.
- USE OF SYNTHETIC BURLAP AND TWINE IS PROHIBITED.
- AFTER REMOVAL OF BASKET TOP HORIZONTAL RING(S) AND LOOPS, TWINE CAN BE RETIED OVER TOP OF ROOT BALL TO STABILIZE TRUNK THROUGH FIRST YEAR. SEE DRUM LACING ILLUSTRATION FOR RETYING INFORMATION.



- IF ROOT BALL HAS BEEN REBURLAPPED, REMOVE BURLAP ON THE OUTSIDE OF BASKET AFTER ROOT BALL IS PLACED IN THE PLANTING PIT.
- REMOVE ALL BURLAP AND TWINE REMAINING OVER TOP OF ROOT BALL WITHIN ONE YEAR OF PLANTING.

SHOULDER OF ROOT BALL

RETIE TWINE AT WIRE JUNCTIONS TO STABILIZE, NOT MIDWAY BETWEEN JUNCTIONS

HIGH PROFILE PACKAGE